



SCHEDULE OF PRICES

County DuPage  
 Local Public Agency City of Wheaton  
 Section 16-00114-00-FP  
 Route Various

**Schedule for Multiple Bids**

Combination Letter	Sections Included in Combinations	Total

**Schedule for Single Bid**

(For complete information covering these items, see plans and specifications)

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total
1	Dust Control Watering	UT	325.00		
2	One Year Guarantee (Non-MFT)	LS	1.00		
3	Supplemental Watering	UT	150.00		
4	Trench Backfill	CY	1,640.00		
5	Topsoil Furnish and Place	CY	1,798.50		
6	Exploratory Excavation	EA	8.00		
7	Tree Root Pruning	EA	15.00		
8	Seeding, Class 1	SY	3,806.00		
9	Seeding Behind Curb	LF	7,747.00		
10	Erosion Control Blanket	SY	11,943.00		
11	Sodding	SY	11,943.00		
12	Inlet Filters	EA	179.00		
13	Perimeter Erosion Barrier	LF	50.00		
14	PCC Base Course Widening, 7"	SY	1,708.00		
15	Hot-Mix Asphalt - Driveway Pavement, 2"	SY	1,715.00		
16	Aggregate for Temporary Access	TN	150.00		
17	Bituminous Materials (Prime Coat)	GA	17,545.00		
18	Aggregate Prime	TN	90.80		
19	Hot-Mix Asphalt Surface Course, Mix "D",N50	TN	7,420.00		
20	Leveling Binder (Machine Method),N50	TN	7,140.00		
21	Hot-Mix Asphalt Binder Course, IL-19.0, N50	TN	1,000.00		
22	PCC Driveway Pavement, 5"	SY	2,985.00		
23	PCC Sidewalk, 4"	SF	9,705.00		
24	Detectable Warnings	EA	79.00		
25	Combination Curb & Gutter Removal	LF	15,790.00		
26	Hot-Mix Asphalt Surface Removal, Variable Depth	SY	83,804.00		

**RETURN WITH BID**

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total
27	Sidewalk Removal	SF	9,705.00		
28	Driveway Pavement Removal	SY	4,700.00		
29	Class D Patching, Type II, 4"	SY	50.00		
30	Class D Patching, Type III, 4"	SY	50.00		
31	Class D Patching, Type IV, 4"	SY	700.00		
32	Class D Patching, Type II, 9"	SY	30.00		
33	Class D Patching, Type III, 9"	SY	30.00		
34	Class D Patching, Type IV, 9"	SY	1,140.00		
35	Class D Patching, Type II, 12"	SY	35.00		
36	Cold Patch	TN	100.00		
37	Storm Sewers, PVC, SDR-26, 4"	LF	20.00		
38	Storm Sewers, PVC, SDR-26, 6"	LF	20.00		
39	Storm Sewers, PVC, SDR-26, 10"	LF	20.00		
40	Storm Sewers, PVC, SDR-26, 12"	LF	20.00		
41	Storm Sewers, PVC, SDR-26, 8" Water Quality Pipe	LF	20.00		
42	Storm Sewers, PVC, SDR-26, 10" Water Quality Pipe	LF	78.00		
43	Storm Sewers, PVC, SDR-26, 12" Water Quality Pipe	LF	40.00		
44	Storm Sewers, PVC, SDR-26, 15" Water Quality Pipe	LF	20.00		
45	Sanitary Sewers, PVC, SDR-26, 6"	LF	20.00		
46	Sanitary Sewers, PVC, SDR-26, 8"	LF	20.00		
47	Sanitary Sewers, PVC, SDR-26, 8" Water Quality Pipe	LF	92.00		
48	Water Main, DIP, CL52, Push Joints, Trenched, 6"	LF	90.00		
49	Water Main, DIP, CL52, Push Joints, Trenched, 8"	LF	2,422.00		
50	WM, DIP, Restrained Joints, Horiz Directional Drill, 8"	LF	100.00		
51	WM, DIP, Restrained Joints, Trenched & Encased, 8"	LF	24.00		
52	Polyethylene Encasement	LF	2,762.00		
53	Water Valves, 8"	EA	4.00		
54	Fire Hydrants	EA	6.00		
55	Cut & Install Endcaps	EA	2.00		
56	Water Service Line, 1"	LF	500.00		
57	Water Service Line, 1 1/4"	LF	15.00		
58	Water Service Line, 1 1/2"	LF	30.00		
59	Water Service Complete	EA	18.00		
60	Adjust Sanitary Sewer 8" or Less	LF	330.00		
61	Fire Hydrants To Be Removed	EA	4.00		
62	Domestic Water Service Box Replacement	EA	2.00		
63	Manholes 4' Dia, T1FCL, < 8'	EA	4.00		
64	Sanitary Manholes 4' Dia, T1FCL, < 8', Chimney Seal	EA	1.00		
65	Catch Basins, 2' Dia, 3010-A	EA	3.00		
66	Catch Basins, 3' Dia, 3010-A	EA	42.00		
67	Catch Basins, 3' Dia, 3010-L	EA	7.00		
68	Catch Basins, 3' Dia, 3210-A	EA	5.00		
69	Catch Basins, 3' Dia, 3210-L	EA	1.00		
70	Catch Basins, 3' Dia, T1FOL	EA	1.00		
71	Valve Boxs To Be Adjusted	EA	2.00		
72	Domestic Water Service Box Adjustment	EA	4.00		



**RETURN WITH BID**

Bidder's Proposal for making Entire Improvements

Item No.	Items	Unit	Quantity	Unit Price	Total